

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/12/2022-23 Dated: 26-08-2022

APPROVED TENDER SCHEDULE -'B'

Item 75

Name of Work:-Improvements to drains at B sector and surrounding areas in ward no:05 Yelahanka New Town
Sub Division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri B R Mohan	
				Rate	Rate in Words
1	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work. Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum.(Tipper 5.5 m3)	Cum	311.30	316.00	Three Hundred Sixteen Only
2	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse	Cum	46.70	5773.00	Five Thousand Seven Hundred SeventyThree Only
3	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.	Tonne	5.35	95810.00	NinetyFive Thousand Eight Hundred Ten Only

Executive Engineer
Yelahanka Division
Yelahanka ZoneBruhat Bangalore Mahanagara Palike
BANGALORE - 560084

	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	89.14	6513.00	Six Thousand Five Hundred Thirteen Only
5	Providing and fixing precast reinforced cement concrete covering slabs of 10Cm thick made of M25 with OPC cement,@340kgs/cum with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work.	Sqm	254.70	1958.00	One Thousand Nine Hundred FiftyEight Only
6	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	t.Km	398.46	100.00	One Hundred Only


Signature of the
Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.